



420 Rail Street
Negaunee, MI 49866
906-475-6616
WWW.NDW.US

ADDENDUM

Number: 1	Project Number: 2339
Project: Marquette Sawyer Regional Airport Holdroom Expansion	Date: March 11, 2024

The contractor shall acknowledge receipt of all addenda by listing the number where indicated on the bid form.

Drawings, specifications, and / or proposals are herein amended, expanded, and / or modified, and become a part of the Contract Documents with the same effect as if incorporated in the original documents. Any contrary provisions contained, or referred to, in Drawings and / or Specifications, shall remain applicable unless overridden by this Addendum. Revised provisions herein shall include all labor, materials, methods, modifications, etc. required for the completion of the Work.

Specification Modifications:

None

Drawing Modifications:

None

Clarifications:

1. Attached specification section 26 51 00 – Interior Lighting was missing from the specification PDF.
2. As discussed during the pre-bid meeting, anyone working on the project will need to acquire a badge through the airport office or be escorted by a badged employee.
3. Bottom of bar joists above acoustical tile ceiling is approximately 13'-6" above the floor.

Attachments: 26 51 00 – Interior Lighting

End of Addendum

Section 26 51 00 Interior Lighting

PART 1 - General

- 1.1 Summary
 - A. Section includes interior luminaires and accessories.
- 1.2 Submittals
 - A. Shop Drawings: Indicate dimensions and components for each luminaire not standard product of manufacturer.
 - B. Product Data: Submit dimensions, ratings, and performance data.

PART 2 - Products

- 2.1 Interior Luminaires
 - A. Product Description: Complete interior luminaire assemblies, with features, options, and accessories as scheduled.
 - B. Substitutions: Section 00 21 00 – Instructions to Bidders.

PART 3 - Execution

- 3.1 Existing Work
 - A. Disconnect and remove abandoned luminaires, lamps, and accessories.
 - B. Extend existing interior luminaire installations using materials and methods compatible with existing installations, or as specified.
 - C. Clean and repair existing interior luminaires to remain or to be reinstalled.
- 3.2 Installation
 - A. Locate recessed ceiling luminaires as indicated on reflected ceiling plan.
 - B. Install surface mounted luminaires plumb and adjust to align with building lines and with each other. Secure to prevent movement.
 - C. Install clips to secure recessed grid-supported luminaires in place.
 - D. Install wall-mounted luminaires at height as indicated on Drawings.
 - E. Install accessories furnished with each luminaire.
 - F. Make wiring connections to branch circuit using building wire with insulation suitable for temperature conditions within luminaire.
 - G. Ground and bond interior luminaires in accordance with Section 26 05 00.
- 3.3 Field Quality Control
 - A. Operate each luminaire after installation and connection. Inspect for proper connection and operation.
- 3.4 Cleaning
 - A. Remove dirt and debris from enclosures.
 - B. Clean photometric control surfaces as recommended by manufacturer.
 - C. Clean finishes and touch up damage.
- 3.5 Schedules
 - A. Exit Signs:
 - 1. Sure-Lite APX7R.

End of Section