



Notice to Bidders for Letting of August 12, 2025

ADDENDUM NO. 1 – Issued August 8, 2025

REQUEST FOR PROPOSALS – HANGAR 663 CONCRETE FLOOR REPAIR AND REPLACEMENT MARQUETTE SAWYER REGIONAL AIRPORT

This Addendum changes the terms of the Bid Proposal. By submitting a bid, you accept all changes included in this Addendum. Bidders are required to acknowledge receipt of this Addendum in the space provided on the Proposal Forms.

The following paragraphs and the attached pages will instruct you as to the changes made and how to make them.

CHANGES TO BID ITEM PAGES

When you are instructed to **ADD, DELETE, or MAKE CHANGES** to a **BID ITEM PAGE OR PAGES**, these additions, deletions, or changes **MUST** be made on the bid item pages you submit with your bidding proposal, whether handwritten or computer generated.

CHANGES TO OTHER PAGES

When you are instructed to **DELETE** something which is **NOT** on a Bid Item Page, you may line through the text diagonally and/or print or write the word “**DELETE**” on the text being deleted. Physically removing the page(s) is not necessary.

When you are instructed to **ADD A NON-BID ITEM PAGE(S), OR PORTIONS THEREOF**, you **MUST CONSIDER** it/them in developing your bid, but the physical insertion of the new page(s) into the proposal is not necessary.

FAILURE TO CARRY OUT THE INSTRUCTIONS IN THIS ADDENDUM MAY RESULT IN THE REJECTION OF YOUR BID.

REQUEST FOR PROPOSALS –
HANGAR 663 CONCRETE FLOOR REPAIR AND REPLACEMENT

Prospective bidders on the above project are hereby advised of the following changes:

PROJECT CHANGES:

1. Page 1, Title

Specification: Request for Proposals (RFP) – Hangar 663 Concrete Floor Repair and Replacement

Replace: Request for Proposals (RFP) – Hangar 663 Concrete Floor Replacement

2. Page 2, Technical Provisions

Specification: The County requests quotes to repair/replace multiple sections of the concrete hangar floor in Hangar 663.

Replace: The County requests quotes to replace multiple sections of the concrete hangar floor in Hangar 663.

Specification: Specifications for re-barring includes #7 rebar at 16 in. on center with #7 cross ties at 16in. on center.

Replace: Specifications for re-barring includes #4 rebar at 16 in. on center with #4 cross ties at 16in. on center.

Add: Depth of dowel pins into existing concrete shall be 4 in.

3. Page 2, Proposal Requirements

Delete: 5. Before the project begins, the contractor must work with the property owner (Airport) to install a water meter to monitor water usage. The contractor will be responsible for all water usage costs.

4. Exhibit 2

Specification: Concrete slab with #7 bars at 16”o.c. each way, at 3 ½” clear from top of slab.

Replace: Concrete slab with #4 bars at 16”o.c. each way, at 3 ½” clear from top of slab